BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2024-25/OW/WORK_INDENT3532

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/05/2024-25 Dated: 07-08-2024

APPROVED TENDER SCHEDULE - B

Item-01

Name of Work:-Providing Drinking water facilities to 110 villages areas in Kempegowda ward no 01

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri SADASHIVAMURTHY NARAYANARAO	
				Rate	Rate in words
1	Geophysical investigation at site for sinking borewells for Providing drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergerss method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M 15 b) Above 30 M - 30 (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of	Each	7.00	6425.16	Six Thousand Four Hundred TwentyFive Paise Sixteen Only
2	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete) 0-50Mtr	Rmtr	350.00	449.57	Four Hundred FourtyNine Paise FiftySeven Only
3	50-100 mtr	Rmtr	350.00	563.78	Five Hundred SixtyThree Paise SeventyEight Only
4	100-150 mtr	Rmtr	350.00	599.02	Five Hundred NinetyNine Paise Two Only
5	150-200 mtr	Rmtr	400.00	695.01	Six Hundred NinetyFive Paise One Only
6	200-250 mtr	Rmtr	400.00	815.30	Eight Hundred Fifteen Paise Thirty Only
7	250-300 mtr	Rmtr	400.00	899.13	Eight Hundred NinetyNine Paise Thirteen Only
8	300-350 mtr	Rmtr	400.00	1054.66	One Thousand FiftyFour Paise SixtySix Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri SADASHIVAMURTHY NARAYANARAO	
				Rate	Rate in words
9	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar-Medium duty..	Rmtr	480.00	2348.68	Two Thousand Three Hundred FourtyEight Paise SixtyEight Only
10	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 15.00 HP - 120 LPM @ 266 m = 23 STG Outlet Dia - 2.00"	Nos	7.00	84256.15	EightyFour Thousand Two Hundred FiftySix Paise Fifteen Only
11	Providing Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, to work site as per necessary ammendments and instructions of engineer incharge of work. For 12.50 HP - 90 LPM @ 264 m = 24 STG Outlet Dia - 2.00"	Nos	2.00	77918.47	SeventySeven Thousand Nine Hundred Eighteen Paise FourtySeven Only
12	Supplying and Drawing 3 Core Flat PVC Shelted Submerisible Pump Cable Manufactured With Electrolytic grade copper with flexible copper conductor confirming to table 3 class 5of IS 8130-1984 and Virgin PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts as per IS-694:1990. 3C x 6.0Sqm	Mtr	5200.00	297.69	Two Hundred NinetySeven Paise SixtyNine Only
13	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50mm dia	Each	15.00	1518.81	One Thousand Five Hundred Eighteen Paise EightyOne Only
14	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm	Nos	15.00	1518.81	One Thousand Five Hundred Eighteen Paise EightyOne Only
15	Providing wrought mild steel (galvanized) GI collar confirming to IS 1239-II, 1991 with latest amendments if any For 50 mm dia GI collar	Nos	15.00	324.42	Three Hundred TwentyFour Paise FourtyTwo Only
16	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark 50mm	Each	399.00	3705.89	Three Thousand Seven Hundred Five Paise EightyNine Only
17	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any for	Each	15.00	324.42	Three Hundred TwentyFour Paise FourtyTwo Only
18	Supply, installing,testing and commissioning COMMON control panel consisting of the following INCOMING:1 No set of Phase indicating lamps with SFU of suitable rating 1 No, Analog Ammeter, 1 No Analog Voltmeter 1ni with Phase selector switch, Isolating switch OUTGOING for Main Electrical Pump: 1 No. MCB 1 No. DOL of S/D Starter suitable for respective HP 1 No. Electrcal Protection Like single Phase preventor, under voltage over Volage, under current over current & dry run protection suitable for the pump described above 1 no Indoor type NOTE: 1) DOL- Direct Online Starter 2) S-D- Star Delta Starter etc. complete.6 to 15 HP pumps	Each	8.00	19319.23	Nineteen Thousand Three Hundred Nineteen Paise TwentyThree Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri SADASHIVAMURTHY NARAYANARAO	
				Rate	Rate in words
19	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges,tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work.	Job	8.00	7897.80	Seven Thousand Eight Hundred NinetySeven Paise Eighty Only
20	Fabricating supplying and mounting MS box made out 14SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete.	Sq CM	539250.00	0.61	Paise SixtyOne Only
21	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. Flat with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. 40 x 40 x 6 mm	Mtr	75.00	370.59	Three Hundred Seventy Paise FiftyNine Only
22	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws. F 20" x 20" x 2.5"	Each	15.00	396.26	Three Hundred NinetySix Paise TwentySix Only
23	Labour charges for erection of outdoor type panel board and meter board units with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions of engineer incharge of work	Job	15.00	1761.82	One Thousand Seven Hundred SixtyOne Paise EightyTwo Only
24	Earthing: Suppluing and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts,nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia.	Job	15.00	4264.81	Four Thousand Two Hundred SixtyFour Paise EightyOne Only
25	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.	Each	8.00	3752.06	Three Thousand Seven Hundred FiftyTwo Paise Six Only
26	Supply and delivery at site brand new best make starter/ control panel suitable for following HP centrifugal pump confirming with ISI mark and its latest amendments. 10 to 12 HP centrifugal pump	Each	8.00	43316.39	FourtyThree Thousand Three Hundred Sixteen Paise ThirtyNine Only
27	Yield testing of borewells at final depth with a minimum of 10 hours continuously with the help of pump testing unit including the cost of transportation charges, crew charges and cost of consumables	Each	8.00	19812.54	Nineteen Thousand Eight Hundred Twelve Paise FiftyFour Only
28	1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part-1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm)	Km	0.36	172344.55	One Lakh SeventyTwo Thousand Three Hundred FourtyFour Paise FiftyFive Only
29	LABOUR For Stringing of 1.1 kV grade Aerial Bunched 3 Core cable of XLPE insulation of size (3x95) (Phase Conductor) + (1x70) (Insulated Messenger Neutral) + (1x16) (Street Light Control)	Km	0.36	40228.96	Fourty Thousand Two Hundred TwentyEight Paise NinetySix Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri SADASHIVAMURTHY NARAYANARAO	
				Rate	Rate in words
30	Supplying of TPST with rewirable porcelain channels in SM enclosure. Made out of 14 SWG powder coated paint of approved colour. 32A	Nos	8.00	2066.79	Two Thousand SixtySix Paise SeventyNine Only
31	Supplying and fixing LED Type panel board indicating lamp with required colour Suitable for 220 V AC 50Hz 12/24 V DC Group 'A'	Nos	8.00	625.75	Six Hundred TwentyFive Paise SeventyFive Only
32	Supplying & fixing of Porcelain fuse channel with cutout on existing wooden/panel using necessary nuts, bolts and washers.	Each	48.00	487.23	Four Hundred EightySeven Paise TwentyThree Only
33	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. Flat.....with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. 40 x 40 x 6 mm	Rmtr	40.00	370.59	Three Hundred Seventy Paise FiftyNine Only
34	Supplying Fully Automatic Star- Delta Starter Unit Push Button Type With Suitable Wires 3 Contractors, One Adjustable Thermal Timer Mounted on a Common Base Plate held in Steel Enclosure For Use on 400/440 Volts 3 Phase and Wired after Fixing to the Exisiting Wooden Board For Motor, Above 12.5 HP upto 25 HP	Nos	17.00	10648.66	Ten Thousand Six Hundred FourtyEight Paise SixtySix Only
35	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, including dressing of excavated surfaces, disposing off or leveling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m. Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work. In all kinds of soils. Depth upto 1.50m	Cum	675.00	646.89	Six Hundred FourtySix Paise EightyNine Only
36	Providing PVC ringtite pipes conforming to IS 985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. complete For: PVC pipes 75mm dia., 6 kg/sqcm & class 5	Mtr	1000.00	267.31	Two Hundred SixtySeven Paise ThirtyOne Only
37	Providing PVC ringtite pipes conforming to IS 985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. complete For: PVC pipes 50mm dia., 6 kg/sqcm & class 5	Mtr	2000.00	122.72	One Hundred TwentyTwo Paise SeventyTwo Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri SADASHIVAMURTHY NARAYANARAO	
				Rate	Rate in words
38	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m, and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	540.00	213.85	Two Hundred Thirteen Paise EightyFive Only
39	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	180.00	3420.23	Three Thousand Four Hundred Twenty Paise TwentyThree Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Yelahanka Division
Yelahanka, Bengaluru-64.
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064